May 2010 Flood Nashville, TN

Surprises and Responses

Scott Potter, PE Director





Flood levels changed

 Previously protected properties are no longer flood-proof.





K.R. Harrington WTP plant flooded

o 2nd plant threatened and chemical supply road washed out.

Resources were stranded

- Assistant Director stranded in neighborhood.
- o 160 MWS employees personally affected by flood damage (21%).
- MWS vehicles stuck in flood waters.





Relationships = Resources

AcrossDepartments

VolunteerAgencies

Outside the County









May

Water Quality Threatened

Turbidity


- o May 3, 5am = 146 NTU
- Normal = 9 NTU or lower


May Chemical Costs

- o \$212,473
- o Normally \$50K \$70K

May Electrical Costs

- o \$304,000
- 2X normal monthly cost





Mitigation: K.R. Harrington WTP

- Elevated hot house
- Relocate generators, switch gear
- Add 5th generator = increase capacity to 90mgd
- Seal wall penetrations
- Elevate chemical feed system
- Raise clear well vents



Mitigation = Fix building codes



Community warning systems

Nashville SAFE: EOC

- Inundation mapping
- Timing charts
- Predictive action level maps



NERVE: Public/Media

- Real-time information
- Road closures
- Shelters
- School closings

